

Core-to-Core Program



ICEPP
The University of Tokyo



MEG II 実験背景事象抑制に向けた DLC-RPCの開発 — 新型モジュールの設計と製作 —

神戸大理 高橋 真斗

大谷航^A, 大矢淳史^B, 越智敦彦^C, 鈴木大夢^C, 潘晟^A, 山本健介^B, 李維遠^B,
他 MEG II コラボレーション
(東大素セ^A, 東大理^B, 神戸大理^C)

日本物理学会2024年春季大会 @ Online


- Introduction (reminders)
 - Upstream Radiative Decay Counter in MEG II
 - Problems in First prototype
- Distortion of the electric field
 - Structure of First prototype
 - Structure validation using mock-up
- Insufficient quench distance of discharges
 - Discharge at conductive strips
 - Cover width investigation
- Summary and Prospects

Upstream RDC in MEG II

➤ MEG II searches for $\mu \rightarrow e\gamma$ at Paul Scherrer Institut (PSI)



➤ Radiative Decay Counters;
Detectors for tagging BG- γ from RMD

Resistive Plate Chamber with Diamond-Like Carbon (DLC-RPC)
being developed as **upstream RDC**



First prototype

Radiative Muon Decay (RMD)



- μ^+ beam at upstream RDC
- Low momentum (28 MeV/c)
 - High intensity (7×10^7 /s)

Problems in First prototype

- First prototype for performance evaluation under high-rate μ beam
 - Implement systems to improve rate capability up to 4 MHz/cm²
 - Operation with a four-layer configuration

➤ Problems

- **Distortion of electric field**

- Low quality of spacing pillar formation (reported in previous talk)
- ✓ Non-flatness of stacked electrodes (reported in this talk)


- **Insufficient quench distance for discharge**

- ✓ Insulation cover on conductive strips (reported in this talk)


→ **Made the DLC-RPC operation unstable**

→ **Need to improve the structure**


Distorted spacing pillar



Non-flatness of electrodes




Discharge at conductive strip




- Introduction (reminders)
 - Upstream Radiative Decay Counter in MEG II
 - Problems in First prototype
- Distortion of the electric field
 - Structure of First prototype
 - Structure validation using mock-up
- Insufficient quench distance of discharges
 - Discharge at conductive strips
 - Cover width investigation
- Summary and Prospects

Structure of First prototype

Inner overview of First prototype




Electrode



3 cm x 3 cm active region

Cross-section scheme



What distorted the electric field?

➤ Constraints distorting electrodes


1. **Alignment pins** for precise stacking of electrodes

→ Misalignment of holes and pins due to accuracy during fabrication


2. **Adhesive** for electrode fixation and gas tightness

→ Technical difficulty in maintaining flatness during electrode installation

→ Remove these constraints



The adhesion area is line position



1. Misalignment of fixing position on substrate and film


Change the structure

➤ Adhesive-free structure

- Electrode fixation by tape (detachable and fine-tunable)
- Extend the outermost films to the outside of the O-ring to make it gas-tight
→ Tape is for adjustment and substantial electrode fixation is by O-ring

➤ Alignment pins are placed outside the chamber


- Causes gas leaks when placed inside the chamber
- Slightly reducing alignment accuracy



Fabrication of mock-up: substrate

➤ Full-scale size

- Φ 30 cm/ Φ 28 cm of substrates (Φ 20 cm of an active region)





Fabrication of mock-up: spacers

➤ Spacers

- Made of Kapton tape
- $\sim 350 \mu\text{m}$ in thickness
- 2 – 3 mm square
- 2 cm pitch

(Actual design)




- Made of photolithographic technology
- $\sim 330 \mu\text{m-t}$
- $\Phi 400 \mu\text{m}$
- 2.5 mm pitch



Fabrication of mock-up: inner foil

➤ Inner foil

- Φ 20 cm active region
- structure to be fixed outside the chamber




Fabrication of mock-up: HV supply line

➤ HV supply line formed by sputtering




- Formed on foils connected to the outside

The sputtered layer of a conductive pattern




• Covered with insulation

- Cover thickness: 75 μm
→ Insulation cover is reproduced
 - 100 μm thickness







Cross-section view at HV supply line



O-ring straddles insulation cover
→ Can cause gas leakage

Fabrication of mock-up: gas system

- The tube, the foil, and the substrate are adhered



- The only constraint

However,

- small area
- it is possible to make sufficient adjustments before adhesive

→ Small impact on flatness

Structure validation: flatness



- No foil distortion was observed in multiple inner layers

Good flatness of foils


1 inner layer

3 inner layers

Assembly




If flatness is bad...




Φ 30 cm (active region Φ 20 cm)

Structure validation: gas tightness


- Many gas leaks at the HV supply line
 - Especially in the case of multiple inner layers




➔ Need to improve the structure



Differential pressure between inside the chamber and atmospheric pressure



- Create an insulating cover over the entire O-ring location to eliminate steps




Summary of structure studies

- Removed constraints in First prototype
 - Alignment pins and adhesion fixation of electrodes
- Fabricated full-scale mock-up
 - **Flatness of electrodes was sufficient**
 - **Gas tightness of the chamber should be improved**
 - Structure that eliminates steps in the insulation cover
 - Important findings in the construction of the full-scale module
 - Techniques for flattening electrodes
 - Problems in handling
- To be done
 - Design with other systems implemented



- Introduction (reminders)
 - Upstream Radiative Decay Counter in MEG II
 - Problems in First prototype
- Distortion of the electric field
 - Structure of First prototype
 - Structure validation using mock-up
- Insufficient quench distance of discharges
 - Discharge at conductive strips
 - Cover width investigation
- Summary and Prospects

Insufficient quench distance

- Insulation cover on conductive strips
 - Conductive strip: improve rate capability
 - Insulation cover: avoid discharges at the conductive pattern



Simulated the electric field on the insulation cover




Need to investigate safe insulation cover width

Cover width investigation (ongoing)


➤ Previous investigation (reported in JPS spring 2023, 23pT2-5)

- Test using a hand-made insulation cover
- Margin between conductive strip and cover: 500 – 700 μm
- Confirmation of improved operation voltage by widening margins



➤ Planned to fabricate samples with various cover widths and test

- How much margin is required?
- Insulation covers become inactive areas
→ Width is determined based on acceptance



Summary

- The DLC-RPC is being developed as upstream RDC in MEG II
 - Planned to be installed in a high-intensity and low-momentum μ beam
 - First prototype was fabricated for performance evaluation in a high-intensity μ beam
- Problems in First prototype
 - **Distortion of electric field**
 - Low quality of spacing pillar formation (see previous talk)
 - Established high-quality spacing pillars and confirmed operation
 - Non-flatness of stacked electrodes
 - Changed the substrate structure and validated the flatness of the new structure
 - **Insufficient quench distance of discharges**
 - Insulation cover on conductive strips
 - Fabrication samples with various cover widths and test using it


Prospects for the fabrication of the next module and the full-scale module are now in sight

Prospects


- Study for the problems in First prototype
 - Testing to determine insulation cover width will take place in April – May
 - Fabrication of the next module will start in May – June
- Beam test will be conducted using actual μ beam at PSI this year
 - Performance evaluation in a high-intensity μ^+ beam
 - Demonstration for requirements of upstream RDC
 - Feedback on full-scale module design
- Aim to install at the MEG II 2025 physics run

Backup

μ^+ beam/RMD e^+ distribution






μ^+ beam ($\sigma = 2.0$ cm)





RMD e^+ ($\sigma = 2.8$ cm)

First prototype (2022)




Concept of First prototype

- Systems inside and outside the O-ring are fed through the interior of the substrate
 - HV supply lines, signal lines, gas input/output ports
- Avoid covering the substrate surface with the outermost electrode
 - Needed the adhesive for gas-tight




Signal readout

- Signal readout is performed by aluminum strips
- Aluminum strips are formed by etching after being deposited on electrode foils



- Aluminum strips bonded to conductive pads on substrate




Mock-up assembly flow


1. Support frame (bottom)



2. Bottom board




3. Implement inner foils (×3)




4. Implement O-ring



5. Top board





6. Support frame (top)




Implement inner foils



- 8 wings are fixed to the substrate with tape
- Fine-tune tension to prevent foils from distorting




Concept of HV supply lines




HV supply lines



Gas tightness with single inner layer



→
~35 min.




Differential pressure between inside chamber and atmospheric pressure

Pressure in the chamber

- DLC-RPC will be operated under negative pressure

If positive pressure ...



Gas gaps become wider

