



# COBRA MAGNET STATUS

W. OOTANI

JUNE 27TH, 2006 MEG REVIEW



# FIELD MEASUREMENT




---

- Final field measurement was done in February as scheduled.
- Measurement summary
  - COBRA field
    - $I_{SC}=360A$   $I_{NC}=320A$
    - $|z| < 110cm$   $\Delta z=2cm$ ,  $-4cm < R < +29cm$   $\Delta R=2cm$ ,  $0^\circ < \varphi < +330^\circ$   
 $\Delta\varphi=30^\circ$
    - 22644 points
  - BTS fringe field
    - $I_{BTS}=200A$  (unlike polarity)
    - $-110cm < z < 0cm$   $\Delta z=2cm$ ,  $-4cm < R < +29cm$   $\Delta R=2cm$ ,  $0^\circ < \varphi < +330^\circ$   
 $\Delta\varphi=30^\circ$
    - 11424 points
  - Field stability measurement with NMR



# COBRA FIELD STABILITY

- Stability of the COBRA field was measured over a week with NMR at the magic point.
- COBRA field is stable within <20ppm.





# COBRA FIELD MAP



---

- We are finishing the analysis.
- Measured data
  - Correction for Hall-sensor readout
    - Absolute calibration
    - Temperature compensation
    - Planar Hall effect
  - Correction with the measured position of measuring machine
  - Interpolation bw / measuring points by means of bspline surface fitting.
- Calculation
  - Detailed coil modeling
  - Thermal expansion at low temperature ( $\sim -0.4\%$ )



# COBRA FIELD MAP, CONT'D


- Comparison with calculation to check the validity of the measurement
  - The measured field is in agreement with the calculation within 0.22%( $\sigma$ ) all over the volume.
  - Center of field difference distribution  $\sim 0$
  - Not a random deviation
  - Difficult to judge which is right.
- Possible usage
  - Measured data for  $|z| < 1100\text{mm}$   $R < 290\text{mm}$  and calculation for the other regions.






# QUENCH PROBLEM

- There were frequent quenches in the COBRA magnet.
- We found that it is caused by the external noise on the input signal line of the quench detector.
- It seems that they happen mostly at the beg. and the end of the working time.
- Modified shielding and grounding scheme are being tried.
- No quench for the past three weeks, but with zero coil current.
- Looking for the noise source in parallel.



Grounding scheme of COBRA system





# FRINGE FIELD PROBLEM

---

- A dramatic reduction of beam rate was found in  $\pi$ M3 beam line last month when the COBRA ON.
  - Reduction: 30% @ GPS, 95% @ LTF
  - Transverse component causes diffraction of the beam.
- There is an effect also at  $\pi$ E3 beam line, but it's not serious once the field is stabilized.
- Possible solutions @  $\pi$ M3
  - Shielding on beam pipe with high- $\mu$  material
    - Installation of Parmalloy sheet ( $\mu = 180000$ ) was done last week.
    - Shielding factor  $\sim 400$  is expected.
  - Retune the beam line
  - Add horizontal steering magnet
  - Soft iron wall bw /  $\pi$ M3 and  $\pi$ E5
    - The effect is being calculated.





# FRINGE FIELD PROBLEM, CONT'D

- Shielding with high permeability material (Permualloy  $\mu=180000$ ) was installed in the  $\pi$ M3 beam line last week.
- The effect will be measured on Jun. 26th.

